ADDENDUM NUMBER FOUR (4)

CATAWBA COUNTY

BLACKBURN RESOURCE RECOVERY FACILITY OPERATOR'S BUILDING

PROJECT NO. 26.00701

This Addendum Number Four (4) is issued this the 2nd day of November 2026, to all parties who hold a set of Bid Documents for the project entitled: **"BLACKBURN RESOURCE RECOVERY FACILITY OPERATOR'S BUILDING".** This Addendum Number Four (4) shall become part of the Contract Documents and its receipt acknowledged on the bid documents at the time of bidding.

The following additions, revisions, and/or clarifications shall be made to the Contract Documents:

Questions

1. Specification Section 260533, Part 3.1 Raceway Application requires Fiberglass (RTRC) or PVC Schedule 40 for raceways concealed in ceilings and interior walls/partitions. Please confirm this requirement applies to the new office areas, including above ACT ceilings and within gypsum board walls/ceilings.
    a. This can be Type MC cable in lieu of the installing in fiberglass or PVC raceway.
2. For the new dry, non-corrosive office areas, please confirm whether Type MC cable may be used for branch circuits serving lighting, receptacles, and similar loads. where permitted by NEC.
    a. Yes, Type MC cable can be used.
3. Reference in the specifications Bid Schedule Item #24 Landscaping as outlined in Section 013000 Measurement and Payment: It states ".....the lump sum price shall include all material, equipment and labor for the complete installation of the Landscaping as required by the Catawba County Planning Dept. ....." There is not a landscaping plan and plant list included in the set of drawings. There are two areas labeled as "Landscape Area" in front of the existing building on Sheet C-001. Please advise the scope of work which the contractor is to include for Bid Schedule Item #17.
    a. At the time of bid issuance, guidance had not been received from the Catawba County Planning Department on required landscaping elements. After the plan review, though, no extensive landscaping plan will be required. The only landscaping that will be required is seeding and establishing a stand of grass in disturbed areas. The "Landscape Area" notations on Sheet C-001 indicate existing conditions and are not proposed elements to be included in the bid.

This Addendum Number Four (4) is issued this the 2nd day of November 2026.



McGILL ASSOCIATES, P.A.
CONSULTING ENGINEERS
ASHEVILLE, NORTH CAROLINA
26.00701

END OF ADDENDUM NO. 4